Montandon Water Booster Pumping Station

Client: Pennsylvania-American Water Company – Milton District W. Chillisquaque Twp., Northumberland Co., PA

Year: 2022 Cost: \$750,000







Gwin, Dobson & Foreman designed a new water booster station for the Montandon area of the Pennsylvania-American Water Company - Milton District. The station replaced an existing pumping facility that had reached the end of its useful life. Three new booster pumps were installed, each with a capacity of 500 gpm.

GD&F provided all design phase services including electrical, mechanical and site-civil elements. The project included a pre-engineered building, pump station controls, telemetry system, SCADA integration and emergency generator with transfer switch. GD&F also provided construction support services including review of shop drawing submittals and land development approvals.

